



Village of Shorewood

Capacity, Management, Operations and Maintenance 2013 Annual Report

This report is submitted in compliance with provisions of the Satellite Stipulation between the State of Wisconsin and the Village of Shorewood (*State of Wisconsin v. Milwaukee Metropolitan Sewerage District, et. al.* Case No. 2005-CS-000013) as well as the stipulation entered between the State of Wisconsin and the District (*Stipulation – State of Wisconsin v. Milwaukee Metropolitan Sewerage District.* Case No. 02-CS-2701).

June 2014

SECTION 1 PROGRAM OVERVIEW

A Capacity, Management, Operations and Maintenance (CMOM) Plan is required to comply with the Satellite Stipulation between the State of Wisconsin and the Village of Shorewood. The overall intent of the CMOM Plan is to reduce sanitary sewer overflows (SSOs) in accordance with regulations.

1.1 REPORT PURPOSE

The CMOM Program annual report provides summary descriptions of Village of Shorewood CMOM Program activities. The report serves four general purposes:

1. To provide an overview of the activities completed under the CMOM Program on an annual basis;
2. To describe and document changes to the CMOM Program documentation on an annual basis, including changes to objectives, strategies, tactics and performance measures;
3. To describe the activities that are planned or currently being undertaken under the CMOM Program; and
4. To continue compliance with the 2005 Satellite Stipulation between the State of Wisconsin and the Village of Shorewood.

1.2 PROGRAM SUMMARY BY PLAN

The Village's CMOM Program includes a Management Plan, Operation and Maintenance Plan, Capacity Plan, Overflow Response Plan, Condition Assessment Plan, Communications Plan and Audit Plan. Performance measures are included in the Management Plan but are discussed separately below.

Management Plan

The Management Plan outlines the approach developed to implement the CMOM Plan. The successful implementation of a CMOM program is directly related to an organization's structure and communications. Shorewood's Management Plan describes the Village's Sewer Utility governance and the Village's collection system organizational structure; outlines legal authority; identifies asset/fiscal and data management programs; addresses design, construction and inspection standards; speaks to training and education; and introduces performance measures.

Operation and Maintenance Plan

Operation and Maintenance (O&M) Programs for the collection system are critical to properly operate and maintain the collection system and to provide recommendations for future rehabilitation and replacement projects. The Village has historically inspected and cleaned sewers and manholes on a routine basis. These inspection programs are necessary to determine structural integrity, root problems, illegal connection and I/I issues. Other tools and programs as noted are also utilized on an as-needed basis to maintain the system.

Capacity Plan

The Village is required to have sufficient capacity during dry weather events and to manage peak wet weather flows. The Village has an on-going inspection program to identify infiltration and inflow. Wet weather event issues and sanitary sewer overflows are analyzed to determine the root cause of the problem.

Overflow Response Plan

The Village of Shorewood’s Overflow Emergency Response Plan includes written procedures for responding to a sanitary sewer overflow. The Plan incorporates the ORP as a standard operating procedure which directs the response to the SSO, outlines procedures to address investigation of overflows at specific sites, identifies processes for the notification of stakeholders and addresses root cause failure analysis.

Detailed records of emergencies and responses are to be documented with the plan regularly reviewed and revised as necessary in response to the adequacy of past emergency actions.

Condition Assessment Plan

A condition assessment program involves documentation and inspection of the collection system to assess the condition of infrastructure. The information gathered during the assessment is used to plan and budget for repair, rehabilitation and replacement of the assets. Recommendations for additional inspections and cleaning are made from these assessments. Key elements of the condition Assessment Program include

Communications Plan

The Shorewood Sewer Utility communicates with the WDNR, the MMSD the Village Board and its customers on a regular basis.

Audit Plan

A CMOM Audit is necessary to ensure that the Plan is properly implemented, goals and objectives are met and performance measures are reviewed, evaluated and updated on a regular basis.

Key Performance Indicators

Table G-1 Village of Shorewood Performance Measures				2013
DESCRIPTION	GOALS			REPORTED
SEWERS				
Total Sewer Length in Feet	158,400			
Sewers cleaned (Feet/year – ft/yr)	20%	31,000	ft/yr	13,427
Sewers inspected	14%	22,629	ft/yr	13,427
Sewer Failures/year		0	each	0
MANHOLES (MH)				
Number of Manholes in System	1,062			
Manholes inspected	20%	212	MH/yr	25
REHABILITATION/REPLACEMENT DESCRIPTION				
Numbers of manholes repaired		2	MH	0
Number of manholes replaced		0	MH	0
Sewer Rehabilitated (Lined, Grout, Point Repair)		3,000	feet	4,332
Sewer Replaced		TBD	feet	0
Lateral Rehabilitated (Lined)		TBD	Feet	5,775
MAINTENANCE ACTIVITIES				
Root Removal		350	feet	0
Smoke Testing		1500	feet	0
Dye Water Flooding		1500	feet	0
Flow Monitoring percent of the collection system		10	%	10
COLLECTION SYSTEM PROBLEMS				
Basement backups from Village sewers		0	each	0
Basement backups from Private property laterals		0	each	7
Total number of backups		0	each	7
Number of Sanitary Sewer Overflow Occurrences		0	each	0

1.3 Significant Activities

The private lateral lining program recommended in the Village's 2011 Comprehensive Sewer Facility Plan was implemented in 2013, with a total of 90 laterals lined in the identified 2012 and 2013 project areas (the 2012 program was delayed due to the 2012 Basin 6 Sewer Improvement project in that area). Additionally, a total of 4,332 feet of eight inch through 15"x24" sewer pipe were lined.

SECTION 2 MANAGEMENT PLAN IMPLEMENTATION AND ONGOING ACTIVITIES

2.1 Background and Information

The Management Plan describes the approach taken by the Village of Shorewood to implement and operate a continuous CMOM plan. Staff reviewed each of the Management Plan sections during the reporting year to reaffirm the objectives. No changes are proposed to the Management Plan.

2.2 Mission Statement

There are no changes to the mission statement for this report.

2.3 Goals

The goals outlined in the original plan submission have been reaffirmed.

2.4 Organizational Structure

No changes to the Village's organizational structure have occurred during the reporting year.

2.5 Management of Assets

During the reporting year, no significant changes were made to the Village's Asset Management Program approach.

Operation and Maintenance Programs

No changes were made to the operations and maintenance programs identified in the plan.

Condition Assessment

Field assessments were completed.

Equipment Inventory

No significant additions/deletions were made to the Village's equipment and spare parts inventory during the reporting year.

Critical Structures

No changes are proposed to the critical infrastructure identified in the plan.

2.6 Customer Service

No significant changes were made to the customer service section of the plan. Regular web updates were utilized and DPW staff attended a number of customer service training sessions.

2.7 Legal Authority

No changes occurred during the reporting year.

2.8 Fiscal Programs

The utility has been focusing efforts on replacement of major infrastructure components of our system in the last several years due to substantial flooding that occurred in 2010. We continue to replace and repair equipment on an annual basis and are not engaging in any level of capital deferment.

2.9 Data Management

Sewer Utility personnel continue to add data to the Village’s GIS system. The system underwent a major upgrade in 2013.

2.10 Standard Design, Construction and Inspection

The Village regularly reviews its standard specifications for the development and design of sewer system improvements. No changes were made in 2013.

2.11 Training

Shorewood Sewer Utility staff attended several collection system-related training sessions. All field personnel attended the MMSD’s annual Inspection conference. All management staff attended the District’s 2013 CMOM conference.

2.12 Performance Measurements

As noted in the CMOM plan, an annual review of performance measures was completed to evaluate accomplishments and areas for improvements. Please see Section 1.2 for performance measurement data. Though not all goals were met, no changes to the standards are proposed at this time. Staff will continue to evaluate the performance measures over the course of the next several years.

SECTION 3 OPERATION AND MAINTENANCE PLANS AND ONGOING ACTIVITIES

There are no changes proposed to the Village’s O&M Programs. While the goals for the various inspections programs were not all achieved, staff will continue to evaluate the benchmarks in the future to determine if they are achievable in a typical year.

Please see Attachment A for a complete listing of all 2013 inspection and inventory results.

SECTION 4 CAPACITY PLAN AND ONGOING ACTIVITIES

4.1 Background and Information

Implementation of the recommendations from the Facility Plan, adopted in May 2011 began in 2012 and will be implemented over several years.

4.2 Capacity

The Village has no dry weather capacity restrictions.

4.3 Field Investigation

Field inspections were performed on a regular and as-needed basis during the reporting year.

4.4 Flow Modeling

No flow modeling occurred in 2013.

4.5 Flow Monitoring

Flow monitoring occurred in the Basin 6 Phase I construction area. This data is currently being evaluated.

4.6 I/I Reduction

The Village's 2013 annual (public) I/I program included the lining of 4,322 lineal feet of mainline sewer pipe. In its first year of implementation, the private I/I program included 5,775 lineal feet of private sewer lateral rehabilitation.

4.7 Peak Flow Performance Standards

The Village's performance standards were developed in consideration of the District's Peak Flow Performance Standards. Please refer to Table G-1 above.

SECTION 5 OVERFLOW RESPONSE PLAN AND ONGOING ACTIVITIES

5.1 Background and Information

No significant changes are proposed for the Village's Overflow Response Plan.

5.2 Procedure

No significant changes are proposed to the Village's procedures and notifications.

5.3 Overflow Structures

No changes were made to the existing overflow structures during the reporting year.

5.4 Notification

No overflows occurred.

5.5 Weather Forecast

The Village utilizes local and national broadcast television and cable weather channels for forecasting. All DPW employees have convenient, 24-hour access to broadcast weather reports at the PW facility.

5.6 Root Cause Failure Analysis

N/A

SECTION 6 CONDITION ASSESSMENT AND ONGOING ACTIVITIES

6.1 Background Information

The Shorewood Sewer Utility staff regularly inspects and documents the condition of the collection system infrastructure. It is, and has always been, standard practice to use the information gathered during these regular assessments to plan and budget for repair, rehabilitation and replacement of the collection system assets.

6.2 Condition Assessment Key Elements

There have been no changes proposed to the Operations and Maintenance Plans as noted in Section 3.

6.3 Condition Assessment Recommendations

Recommendations are made on on-going basis to repair, rehabilitate and replace infrastructure to properly maintain all assets.

SECTION 7 COMMUNICATION PLAN AND ONGOING ACTIVITIES

7.1 Background and Information

Information relating to the Village's collection system operations is shared on a regular basis with the WDNR, the MMDS, the Shorewood Village Board and the residents of the Village on a regular basis.

7.2 Methods of Communication

All policy issues related to finance, operations, personnel and infrastructure planning are determined by the Shorewood Village Board of Trustees based upon recommendations by the Director of Public Works/Utilities, the Village Manager and the Finance Director.

Information is shared on a regular basis with residents and Utility customers utilizing direct mailings, the Village web site, and Village newsletters (electronic and magazine form).

7.3 CMOM Communication

Public discussion regarding CMOM-related topics occurred on a regular basis during the reporting year as a part of the Sewer Facility Planning discussions. Public discussion occurs on this topic each year at both the sewer utility's budget discussion and the Village's annual financial planning meeting.

7.4 Reporting Methods

The Village has fulfilled its reporting requirement to the entities and regulatory agencies as outlined in the CMOM Plan.

SECTION 8 AUDIT PLAN AND ONGOING ACTIVITIES

8.1 Background and Information

The intent of the Audit is to ensure proper plan implementation and regular reviews and updates of performance measures.

8.2 Audit and Review the Plan

Audit shall be performed every five years in accordance with the Stipulation. The first CMOM Audit is required in 2014.

8.3 Monitor the Plan

The Village of Shorewood annual reviews the goals and performance measures to evaluate the program effectiveness.

8.4 Provide Recommendations

The Village's annual review and monitoring will generate necessary recommendations to revise the performance measure and update the Plan.

8.5 Update the CMOM Plan

CMOM plan updates will be based upon the audit, feedback from employees and review recommendations.

CERTIFICATION

I certify that the material contained in this report is, to the best of my knowledge, true, accurate and complete, and that elected officials of the Village of Shorewood have been apprised of the contents of this report.

Leeann Butschlick
Director of Public Works
Village of Shorewood, WI

ATTACHMENT A

Component of Municipal CMOM Annual Report