Legend

Year

2020

2021

Total Marking Length:

Downer - 4-inch Yellow Centerline. No clear pattern currently. In general 15-foot long markings with a 15-foot gap. Longer gaps at intersections. Some longer markings before intersections. Assume 50% of the length for a quantity.

4-inch Yellow Marking - 1,325 LF
12-inch White Crosswalk (Across Downer at Shorewood Boulevard) - 176- LF
~~6-inch White Crosswalk (Across Shorewood Boulevard) - 128 LF~~
12-inch Stop Bar (Shorewood Boulevard and Oakland Avenue) ~~44~~ LF
12

Markings should be outside mill and overlay limits.

Markings should be outside mill and overlay limits.

No Markings

Pavement Joint here.

44-ft wide times 4

~~Pavement Joint here.~~

No Markings

~~stop bar 16-ft~~

~~stop bar 16-ft~~

~~32-ft wide times 4~~

Stop bar partially on Asphalt and concrete. 12-LF

No Markings

Markings outside paving limits.

No Markings

No Markings

No Markings

~~Cross walks 32-ft times 2, in newly paved area.~~ Outside of project paving limits.

~~Cross walks 32-ft times 2.~~ Markings should be outside mill and overlay limits.

~~Cross walks 27-ft, 21-ft, 25-ft, 19-ft.~~ Markings should be outside mill and overlay limits.

Stop bar 16-ft, outside paving limits of this project.

Yellow Center Line

Markings all past joint line.

Sources: Esri, HERE, Garmin, Intermap, increment P Corp., GEBCO, USGS, FAO, NPS, NRCAN, GeoBase, IGN, Kadaster NL, Ordnance Survey, Esri Japan, METI, Esri China (Hong Kong), (c) OpenStreetMap contributors, and the GIS User Community

0 100 200 400 Feet

PROPOSED SE AREA MILL AND OVERLAY PROGRAM

VILLAGE OF SHOREWOOD
MILWAUKEE COUNTY, WISCONSIN

STRAND ASSOCIATES

FIGURE 1
3646.011

Path: S:\MIL\3600--3699\3646\011\Drawings\GIS\Figures\Mill and Overlay New 11x17.mxd User: Danc Date: 6/28/2019 Time: 7:26:44 AM